



Addendum No. 1
2018 Clearing Contract (EN-301)

September 20, 2018

Item #1 – Clarifications

The following clarifications supersede any specifications within the contract information book.

1. All noted roundabout, roadway, and/or culvert projects are FUTURE projects BY OTHERS and not included in this project. Project scope is limited to the clearing, demolition, staking, and similar work called out the plans.
2. All R/W staking shall be in place at the completion of the Contractor's work. If the Contractor's operations damages any staking, it shall be replaced at no cost to the owner.
3. Contractor shall keep the street clean of debris and mud. All disturbed areas shall be covered with two inches of mulch. All excess mulch and other debris from the project shall be removed. The cost of this work shall be included in the submit unit prices.

Please acknowledge receipt of this Addendum by sending an email to jhellmann@noblesville.in.us

CITY OF NOBLESVILLE

James J. Hellmann, P.E. – Assistant City Engineer

