

**2020 Street Rehabilitation - Contract I
Contract: EN-320-01**

ITEMIZED PROPOSAL

BASE BID						
Item No.	Description	Quantity	Unit	Unit Price	Extended Price	
1.0	Maintenance of Traffic	1	LSUM			
2.0	Mobilization/Demobilization	1	LSUM			
3.0	Curb, Concrete, Removal	200	LFT			
4.0	Curb, Concrete, Construction	200	LFT			
5.0	Concrete, Removal	206	SYS			
6.0	Curb Ramp, Concrete, Construction	140	SYS			
7.0	Detectable Warning, Cast Iron, 2'x2', Asphaltic Coating	100	SFT			
8.0	Sidewalk, Concrete, 4", Construction	56	SYS			
9.0	Concrete to Greenspace Conversion (undistributed)	10	SYS			
11.0	Milling, Mainline, 1.25"	10,978	SYS			
12.0	HMA Surface, 9.5 mm, Type B	974	TON			
13.0	HMA for Patching, 8" Depth (undistributed)	150	TON			
14.0	HMA for Wedge & Level	325	TON			
15.0	Manhole/Casting, Adjust to Grade (undistributed)	4	EA			
16.0	Inlet/Catch Basin Rehabilitation (undistributed)	17	EA			
17.0	Line, Thermoplastic, Solid Yellow, 4"	4,200	LFT			
18.0	Line, Thermoplastic, Dash Yellow, 4"	320	LFT			
19.0	Line, Thermoplastic, Solid White, 4"	640	LFT			
21.0	Line, Thermoplastic, Solid White, 6", Crosswalk	200	LFT			
22.0	Line, Thermoplastic, Solid Yellow, 8", Gore	30	LFT			
24.0	Line, Thermoplastic, White, 24", Stop Bar	86	LFT			
26.0	Pavement Message Marking, Thermoplastic, White, Arrow	12	EA			
27.0	Pavement Message Marking, Thermoplastic, White, "ONLY"	12	EA			
31.0	Traffic Signal Loop (undistributed)	16	EA			
32.0	Monument, Section Corner (undistributed)	1	EA			

Base Bid: Total Estimated Construction Costs = _____

CONTRACTOR: _____

ADDRESS: _____

TELEPHONE: _____

FAX: _____

CONTACT: _____

EMAIL: _____