

**Greenfield Avenue Culvert over Lehr Ditch
Contract: EN-297 / OFA026.2010**

ITEMIZED PROPOSAL

BASE BID						
Item	INDOT	Description	Quantity	Unit	Unit Price	Extended Price
1	105-06845	Construction Engineering	1	LSUM		
2	110-01001	Mobilization/Demobilization	1	LSUM		
3	201-52370	Clearing Right of Way	1	LSUM		
4	202-51330	Present Structure, Remove	1	LSUM		
5	202-52710	Sidewalk Concrete, Remove	97	SYS		
6	202-96133	Pipe, Remove	29	LFT		
7	202-99187	Fence, Farm Field, Remove	111	LFT		
8	203-02000	Excavation, Common	225	CYS		
9	203-02070	Borrow	215	CYS		
10	205-06934	Temporary Mulch	3	TON		
11	205-06937	Temporary Silt Fence	946	LFT		
12	205-11591	Temporary Seed Mixture	170	LBS		
13	205-11626	Pump Around	1	EA		
14	207-08266	Subgrade Treatment, Type III	895	SYS		
15	211-09265	Structural Backfill, Type 2	23	CYS		
16	211-09268	Structural Backfill, Type 5	549	CYS		
17	214-12243	Geotextile for Subgrade Type 2A	110	SYS		
18	301-12234	Compacted Aggregate No. 53	170	CYS		
19	306-08034	Milling, Asphalt, 1 1/2 IN.	628	SYS		
20	401-10258	Joint Adhesive, Surface	359	LFT		
21	401-10259	Joint Adhesive, Intermediate	58	LFT		
22	402-07433	HMA Surface, Type B	68	TON		
23	402-07434	HMA Intermediate, Type B	26	TON		
24	402-07435	HMA Base, Type B	37	TON		
25	406-05520	Asphalt for Tack Coat	1	TON		
26	603-99999	Wood Safety Rail	98	LFT		
27	604-05528	HMA for Sidewalk	99	TON		
28	615-06490	Right-of-Way Marker	5	EA		
29	616-06405	Riprap, Revetment	658	TON		
30	616-12248	Geotextile for Riprap Type 2A	703	SYS		
31	621-01004	Mobilization/Demobilization for Seeding	2	EA		
32	621-06553	Seed Mixture R, Modified	3	LBS		
33	621-06560	Mulched Seeding U	2,731	SYS		
34	621-08161	Permanent Turf Reinforcement Mat	181	SYS		
35	715-05048	Pipe, Type 4, Circular, 6 IN.	16	LFT		
36	715-46020	Pipe End Section, Diameter 24 IN.	1	EA		
37	720-44000	Casting, Adjust to Grade (Manhole)	1	EA		
38	720-45410	Manhole, C4	1	EA		
39	720-94840	Casting, Water Valve, Adjust to Grade	3	EA		

**Greenfield Avenue Culvert over Lehr Ditch
Contract: EN-297 / OFA026.2010**

ITEMIZED PROPOSAL

BASE BID						
Item	INDOT	Description	Quantity	Unit	Unit Price	Extended Price
40	723-11111	Structure, Coated Reinforced Concrete, Three-Sided Sections, 180 IN. x 120 IN.	100	LFT		
41	801-04308	Road Closure Sign Assembly	5	EA		
42	801-06625	Detour Route Marker assembly	31	EA		
43	801-06640	Construction Sign, A	11	EA		
44	801-06775	Maintaining Traffic	1	LSUM		
45	801-07118	Barricade, III-A	48	LFT		
46	801-07119	Barricade, III-B	120	LFT		
47	808-06703	Line, Thermoplastic, Solid, White, 4 IN.	516	LFT		
48	808-75245	Line, Thermoplastic, Solid, Yellow, 4 IN.	516	LFT		

Base Bid: Total Estimated Construction Costs = _____ **(Figures)**
 _____ **(Words)**

These prices are the sum of the unit prices multiplied by the quantity for each item. Whereas any mathematical computation error exists causing Total Estimated Construction Costs to be stated incorrectly, the Undersigned acknowledges that the unit prices, as stated above, shall govern.

The above stated items covers all work, labor, equipment, and manpower to complete project. Prospective quoter accepts and agrees to competed the project in accordance to Contract Information Book and Construction Plans.

Respectfully submitted,

 Contractor
 (Individual) (Partnership) or (Corporation)

By: (SIGNED) _____

By: (TYPED) _____

Title: _____

Address: _____

Date: _____

The above Bider acknowledges receipt of Addenda Nos. _____

Note: The legal status of the Bidder, whether as an individual, partnership, or corporation must be indicated as above, and all pertinent information as required by the Specifications must be furnished.